



Site annotations	
1	7 high capacity gullies connecting into piped system
2	1 high capacity gully connecting into piped system
3	7 road gullies connecting into piped system
4	Highway to be reinstated
5	Block paving to be reinstated
6	Barriers around tree pit
7	Site compound access through park gates
8	Attenuation storage tank
9	Trees to be protected from the works
10	Tree canopy
11	Footpath to be reinstated
12	Flows to be discharged into wetland area and wildflower meadow
13	Footpath to be reinstated
14	New wildflower damp meadow to be created
15	Additional area of wildflower meadow

Notes

Revision	Description	Date	By

© Crown Copyright and database right [2017], Ordnance Survey [100019569].



Technical Consultancy  
Place Directorate  
Civic Centre  
Barras Bridge  
Newcastle upon Tyne  
NE1 8QH  
Phone 0191 2787878  
Fax 0191 2114998

MARSHALL POULTON BSc, CEng, MICE  
ASSISTANT DIRECTOR OF TRANSPORT

Project  
Kingsmere Gardens

Drawing Title  
Proposed flood alleviation layout  
Consultation

Status  
Information

Scale	Date
1:750	13/02/2020
	Drawn JPG
	Prepared JPG
	Checked VS
	Original Size A1

TREE SCALE 1:1